

Addendum for Project 42150101  
Pre-Engineered Steel Storage Bldg.

General Contractor:

Approx. 185' of fencing along the west and south side of the new building will need to be removed. Then approx. 225' of new fencing to match existing in type and configuration will need to be installed insuring that it will be a min. of 20' from the newly constructed steel building. See attached updated drawing - C.1.0 for location.

Electrical Contractor:

Add a receptacle for a battery charger. See attached updated drawing E.1.1 for specifications an location.