

IFB 6100044924
Recycled No. 8 Aggregate Specification
02/06/2018

Award Length:

The purchase order validity period will be for 1 year.

Overview:

The Department of Transportation, Allegheny County Maintenance (11-1), is requesting No. 8 SRL=H aggregate from Reclaimed Asphalt Product (RAP); otherwise known as milled materials or millings. The Department will provide the awarded vendor RAP which the vendor will process into Recycled No. 8 SRL=H Aggregate. The recycled aggregate will be delivered to the Department at specified sites.

Material Specification:

This request is for an estimated 14,160 Tons of Recycled No. 8 SRL=H Aggregate to be delivered by the vendor to designated Department stockpiles within Allegheny County.

The requested material may be a recycled No. 8, separated from a bituminous milled material. The No. 8 aggregate delivered to the designated Department stockpile must be free of contaminants, sized to have 100% passing the 1/2" screen, and be SRL=H. Byproducts of the crushing operation remain vendor property. If this remaining material is to be wasted at a fill site, the vendor will provide the Department with proper documentation in accordance with Publication 408, Section 105.14.

Type A, No. 8 virgin limestone aggregate, meeting the requirements of Publication 408, section 703.2 and designated as SRL=H material may be substituted for or blended with the above specified recycled No. 8 aggregate produced from the milled material to achieve a total weight of 14,160 tons of delivered material. Blended material must also achieve SRL=H level. No. 8 virgin aggregate must come from an approved Bulletin 14 source.

The awarded vendor will provide weigh tickets for recycled No. 8 stone delivered to the department stockpiles and the weight of millings returned.

Delivery of No. 8 aggregate will take place between April 15, 2018 & June 30, 2018 as requested by the Department of Transportation. The department reserves the right to change dates as needed within the validity period of the purchase order.

The awarded vendor will be entitled to an estimated 29,700 tons of RAP millings.

All quantities are estimated.

RAP Millings:

An approximate total of 29,700 tons of millings will be delivered to the awarded vendor by the department from department contracted jobs. The millings will be delivered to the vendor's location closest to the current job site/project on that day.

IFB 6100044924
Recycled No. 8 Aggregate Specification
02/06/2018

Delivery of No. 8 Aggregate:

Material is to be delivered, but not limited, to:

5,000 tons	Saxonburg stockpile (0020):	3810 Saxonburg Blvd Indianola, PA 15051
1,500 tons	Monroeville stockpile (0009):	201 Haymaker Rd Monroeville, PA 15146
1,200 tons	Penn Hills VFD Universal(TODA):	125 Universal Rd. Penn Hills, PA 15235
875 tons	Penn Hills Public Works Dept (TODB)	6600 Leechburg Rd. Verona Pa 15147
1,935 tons	Plum Borough Municipal Authority (TODC)	4555 New Texas Rd. Pittsburgh PA 15239
675 tons	SR 910/SR28 South Ramp Harmar (TOHM)	
815 tons	Shaler. Topwship (TODD)	799 Little Pine creek Rd. Shaler, PA 15223
1,050 tons	Sharpsburg Laydown area (TODE)	19th St Sharpsburg, PA 15215
750 tons	West Deer VFD (TOCF)	1520 Saxonburg BLVD. Tarentum, PA 15084
360 tons	SR 8068 Ramp To 28N (TOCD)	199 RTE 908 Natrona heights, PA 15065

TOTAL 14,160 tons

The Department has the right to add and or eliminate Stockpile delivery locations within Allegheny County.

All deliveries will be coordinated with the awarded vendor prior to the required delivery date. Expected delivery time will be within three (3) calendar days after being notified by the Department. The material required delivery rate should be between 300 - 500 Tons/Day, at each location. Delivered material is to be placed in a single location to a height of less than 15 feet.

Provide the Department with two (2) copies of the certified weigh slips daily for the No. 8 aggregate. An AASHTO #8 gradation report will not be required for AASHTO #8 aggregate produced from the milled material.

The vendor will contact the Roadway Programs Coordinator two (2) weeks prior to delivery.

IFB 6100044924
Recycled No. 8 Aggregate Specification
02/06/2018

The vendor will notify the District Materials Engineer at the District 11 Materials Unit two (2) weeks prior to shipping the stockpiled AASHTO #8 material for verification testing and approval of the stockpile. Gradation, wash, and crush count (if applicable) tests will be performed.

Material will not be accepted without approval and applicable testing.

Contact Information:

Tony Beck
Roadway Programs Technician 2
412-781-3260 antbeck@pa.gov

Contact with any Department personnel, except for the purchaser, in regards to this solicitation prior to award is strictly forbidden.

Roadway Programs Coordinator: Scott Kovach, 412-781-3260, sckovach@pa.gov
District Materials Engineer: Brian Myler, 412-429-4820, brmyler@pa.gov