

## **ATTACHMENT C**

### **SPECIFICATIONS**

#### **DISMANTLING - WOVEN WIRE DEER ENCLOSURE**

1. Remove enclosure from all trees, posts, or supports.
2. All enclosure supports that were used to secure the wires to trees and any free standing wooden posts or supports will be removed.
3. All staples that hold wire to trees and/or wooden enclosure supports will be removed.
4. All nails and staples used to fasten enclosure or enclosure supports to trees will be removed.
5. All walk-through and vehicle gates will be removed.
6. All signs will be removed.
7. Any of the above materials considered to be reusable by the Department representative will be delivered to a site designated by the Department representative for salvage for reuse by the Department.
8. All unusable materials are to be removed from the site and properly disposed of by the contractor at the contractor's expense.
9. All materials brought to the work site by the contractor that become waste associated with the dismantling of enclosures, or any personal items inadvertently discarded by the contractor's employees, will be collected and removed from the site at the contractor's expense.
10. Areas of disturbed soil that result from the dismantling and consolidation of fencing materials are to be recontoured, seeded, and mulched at the expense of the contractor.
11. All labor, equipment, tools, etc., needed to complete contracted project are to be provided by the contractor.

CONDITIONS	LEVEL OR DEGREE OF DIFFICULTY	DESCRIPTION
Access to Exclosure Site	0	Exclosure site adjacent to access road
	2	Exclosure site is within 500 ft. of access road
	4	Exclosure site is 501 ft. to 1,000 ft. from access road.
	6	Exclosure site is more than 1,000 ft. from access road
Slope	3	More than half of exclosure perimeter is on a slope of less than 20%
	6	More than half of exclosure perimeter is on a slope of 20% to 35%
	9	More than half of exclosure perimeter is on a slope of more than 35%
Number of Exclosure Posts Dismantled	0	Less than 25% of exclosure supports are exclosure posts
	4	25% to 49% of exclosure supports are exclosure posts
	8	50% to 75% of exclosure supports are exclosure posts
	12	More than 75% of exclosure supports are exclosure posts
Number of Trees to be Removed from Exclosure	0	Average of 1 tree or less per 1,000 feet of exclosure
	4	Average of 1.1 to 2.0 trees per 1,000 feet of exclosure
	8	Average of 2.1 to 3.0 trees per 1,000 feet of exclosure
	12	Average of more than 3.1 trees per 1,000 feet of exclosure
Vegetation Control	0	Less than 10% of the exclosure is entangled or overgrown with vegetation
	4	10% to 30% of the exclosure is entangled or overgrown with vegetation
	8	30% to 50% of the exclosure is entangled or overgrown with vegetation
	12	Greater than 50% of the exclosure is entangled or overgrown with vegetation

Exclosure Dismantling Classification:

The degree of difficulty for exclosure dismantling will be based only on the degree of difficulty within the conditions of: **Access to Exclosure Site; Slope; Number of Exclosure Posts Dismantled; Number of Trees to be Removed from Exclosure; and Vegetation Control.**

- **Moderate** – If the summation of degrees of difficulty total **less than 24**, then the exclosure dismantling project will be classified as **Moderate**.
- **Severe** – If the summation of degrees of difficulty total **24 or more**, then the exclosure dismantling will be classified as **Severe**.