COMMONWEALTH OF PENNSYLVANIA DEPARTMENT OF MILITARY AND VETERANS' AFFAIRS

ANNVILLE, PENNSYLVANIA

JOSH SHAPIRO, GOVERNOR MAJOR GENERAL MARK J. SHINDLER, THE ADJUTANT GENERAL

> PROJECT NO.: ZAWA 192006 / DMVA 42220185 BUILDING 201 DEMOLITION

BIDDLE AIR NATIONAL GUARD BASE, HORSHAM, MONTGOMERY COUNTY, PENNSYLVANIA

DESIGN PROFESSIONALS: OFFICE OF FACILITIES AND ENGINEERING BUREAU OF DESIGN AND PROJECT MANAGEMENT BUILBING 0-10, CHAPEL ROAD, FORT INDIANTOWN GAP ANNVILLE, LEBANON COUNTY, PENNSYLVANIA

INDEX TO DRAWINGS

COVER SHEET

GENERAL CONSTRUCTION

EXISTING SITE/DEMO PLAN NOTES & DETAILS FIGURE 6 MONITORING WELL LOCATIONS BIDDLE ANG UTILITY MAP

ARCHITECTURAL DWGS. N/A STRUCTURAL DWGS. N/A

HVAC CONSTRUCTION

HVAC DWGS. N/A

PLUMBING CONSTRUCTION


PLUMBING DWGS. N/A

ELECTRICAL CONSTRUCTION


ELECTRICAL DWGS. N/A

CODE APPROVALS

PROJECT LOCATION MAP



VICINITY MAP



CAMPUS / KEY PLAN

NO.	DESCRIPTION	DATE
	REVISIONS	

Drawings Listed In Index

DATE ____ BEA Electronic Approval

COMMONWEALTH OF PENNSYLVANIA DEPT. OF MILITARY & VETERANS' AFFAIRS ANNVILLE, PENNSYLVANIA 17003

DESIGN PROFESSIONALS:

OFFICE OF FACILITIES AND ENGINEERING BUREAU OF DESIGN AND PROJECT MANAGEMENT BLDG. 0-10, FORT INDIANTOWN GAP ANNVILLE, LEBANON COUNTY, PENNSYLVANIA

PROJECT NO.: ZAWA 192006 / 42220185

BUILDING 201 DEMOLITION

BIDDLE AIR NATIOANL GUARD BASE HORSHAM, MONTGOMERY CO., PENNSYLVANIA

COVER SHEET


DRAWN BY	DATE	DRAWING
K. LLOYD	1 APR 2023	
CHECKED BY	SCALE	
L. STEFANIK	AS NOTED	



SCALE IN FEET

PROJECT / DEMOLITION NOTES


- THE CONTRACTOR IS REQUIRED TO SUBMIT A REQUEST FOR A DIGGING PERMIT, THROUGH THE BASE CIVIL ENGINEERS OFFICE, BUILDING 232, PHONE NO. (215)323-8335,10 DAYS PRIOR TO CONSTRUCTION. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO VERIFY ALL UTILITY LOCATIONS PRIOR TO THE START OF WORK AND INCLUDE THESE MARKING LOCATIONS ON THE AS-BUILT DRAWINGS.
- 2. ALL UTILITIES HAVE BEEN DISCONNECTED TO THIS FACILITY, PER BASE CIVIL ENGINEERS OFFICE. IF THE CONTRACTOR ENCOUNTERS ANY UTILITY CONNECTIONS, WORK SHOULD BE PAUSED AND THE CONTRACTOR WILL CONTACT THE BASE CIVIL ENGINEER OFFICE IMMEDIATELY FOR FURTHER
- 3. BASE ENTRY/EXIT FOR THE CONTRACTOR WILL BE VIA THE CONTRACTING GATE. ALL VEHICLES WILL BE SEARCHED UPON EACH ENTRY BACK ONTO
- 4. ALL AREAS OF DEMOLITION WILL BE RETURNED TO GRASS. THE CONTRACTOR WILL BE RESPONSIBLE TO PROVIDE APPROXIMATELY 2' OF CLEAN SOIL FILL, 4" OF TOPSOIL, FERTILIZER, STRAW MULCH AND SEED, SEE NOTES AND SPECIFICATIONS. THE FINAL GRADING OF SITE WILL BE GENERALLY LEVEL, ENSURING POSITIVE DRAINAGE TO ANY REMAINING STORM-WATER MANAGEMENT FEATURES, WITHIN THE PROJECT LIMITS, AND MATCHING FLUSH AND LEVEL WITH ADJOINING PAVEMENT EDGES.
- 5. THE CONTRACTOR WILL BE REQUIRED TO PLACE TEMPORARY 6' HIGH CHAIN-LINK SAFETY FENCE AROUND PERIMETER OF PROJECT SITE TO PREVENT ACCESS AND DELINEATE THE PROJECT PERIMETER. EXACT LOCATION OF FENCE TO BE COORDINATED WITH BASE CIVIL ENGINEER'S
- 6. ATTACHED TO THIS PACKAGE ARE MAPS DEPICTING UTILITIES AND MONITORING WELLS, THE CONTRACTOR WILL BE REQUIRED TO CONFIRM ALL HAZARDS WITH THE BASE CIVIL ENGINEERS OFFICE, WITHIN AND ADJACENT TO, THE PROJECT LIMITS, PRIOR TO ANY DEMOLITION WORK.
- 7. 18" FILTER SOCK WILL BE PLACED AROUND THE PERIMETER OF WORK AREA, SEE DETAIL SHEET C.1.1.
- 8. THE CONTRACTOR WILL SAW-CUT CLEAN EDGES WHERE PROJECT LIMITS CROSS EXISTING PAVEMENT AREAS. FINAL SAW-CUT LOCATIONS WILL BE COORDINATED WITH BASE CIVIL ENGINEERS OFFICE PRIOR TO START OF DEMOLITION.
- 9. THE SOIL, PAVEMENT, AND GROUNDWATER ON BIDDLE AIR NATIONAL GUARD BASE HAS BEEN DESIGNATED AS A PFAS/PFOA IMPACTED AREA. THE CONTRACTOR SHALL ASSUME ANY ACCUMULATION OF GROUND WATER OR STORM-WATER RUNOFF, WITHIN THE PROJECT LIMITS, IS CONTAMINATED. IF THE VOLUME OF CONTAMINATED LIQUID IMPACTS THE DEMOLITION OPERATIONS, REQUIRING DE-WATERING, THE CONTRACTOR WILL BE REQUIRED TO COORDINATE WITH PA-DEP AND PROPERLY REMOVE AND DISPOSE OF THE CONTAMINATED WATER TO A CERTIFIED DISPOSAL SITE. ANY MATERIAL DE-WATERING WILL BE COORDINATED WITH THE BIDDLE ANG BASE BASE CIVIL ENGINEER'S OFFICE.



SCALE: 1" = 2,000'

SITE / CIVIL LEGEND

EXISTING	PROPOSED	
450	 [450]	CONTOUR LINE
22	22	SANITARY SEWER
W×	w	WATER LINE
Eux	— Е —	ELECTRIC - UNDERGROUND
E	E	ELECTRIC - OVERHEAD
		FENCELINE
Cux	Cu	COMMUNICATION - UNDERGROUND
——— GAS ———	——— GAS ———	PROPOANE
		STORM SEWER
•	•	WATER VALVE
CL MH RIM = 443.70 INV = 436.85	CL MH RIM = 443.70 INV = 436.85	MANHOLE
447.75	447.75	SPOT ELEVATION
♦ BENCHMARK	⊕ BENCHMARK	BENCHMARK ELEVATION
		FLOW ARROW
-0-	-0-	UTILITY POLE
		FIRE HAYDRANT
		CONCRETE HATCH
		TREE
#	4	POLE MOUNTED AREA LIGHTING
		PENNDOT STANDARD GUIDE RAIL
		WATERLINE CURB STOP
		STORM INLET
YCO	YCO	SANITARY YARD CLEAN OUT
T	T	ELECTRICAL TRANSFORMER W/ VAU
G	G	GENERATOR
C	C	COMMUNICATIONS MANHOLE
	E	ELECTRIC PULL-BOX
		BOLLARD



COMMONWEALTH OF PENNSYLVANIA DEPT. OF MILITARY & VETERAN'S AFFAIRS ANNVILLE, PENNSYLVANIA 17003

|DESIGN PROFESSIONALS:

OFFICE OF FACILITIES AND ENGINEERING BUREAU OF DESIGN AND PROJECT MANAGEMENT BLDG. 0-10, FORT INDIANTOWN GAP ANNVILLE, LEBANON COUNTY, PENNSYLVANIA

PROJECT NO.: ZAWA 192006 / 42220185

> BLDG. 201 DEMOLITION

BIDDLE AIR GUARD STATION MONTGOMERY CO, HORSHAM, PENNSYLVANIA 19044

DEMO SITE PLAN

DRAWING NO. 1 APR 2023 C.1.0

CALL BEFORE YOU DIG!

PA 1 SYSTEM, INC.

1-800-242-1776

POCS SERIAL NUMBER

PENNSYLVANIA LAW REQUIRES 3 WORKING DAYS NOTICE FOR ADJUST SCALE ACCORDINGLY CONSTRUCTION PHASE AND 10 WORKING DAYS IN DESIGN STAGE - STOP CALL

CONTRACTOR SHALL FIELD VERIFY | DRAWN BY ALL DIMENSIONS. VARIANCE FROM CONTRACT DOCUMENTS NOT PERMITTED WITHOUT BUREAU OF ENGINEERING AND ARCHITECTURE APPROVAL.

VERIFY SCALE

BAR IS ONE (1) INCH LONG ON ORIGINAL DRAWING:

IF BAR IS NOT ONE (1) INCH LONG,

K. LLOYD CHECKED BY L. STEFANIK AS NOTED

2-0 STABILIZATION NOTES

- 1. Stockpile heights must not exceed 35'. Stockpile slopes must be 2:1 or flatter.
- 2. Upon completion of an earth disturbance activity or any stage or phase of an activity, the contractor shall stabilize immediately the disturbed areas to protect from accelerated erosion. During non-germinating periods, mulch must be applied at the specified rates. Disturbed areas which are not at finished grade and which will be redisturbed within 1 year may be stabilized in accordance with temporary seeding specifications. Disturbed areas, which are either at finished grade or will not be redisturbed within 1 year, must be stabilized in accordance with permanent seeding specifications.
- 3. Stockpiles must be stabilized immediately.
- 4. Hay or straw mulch must be applied at rates of at least 3.0 tons
- 5. Until the site has achieved final stabilization the contractor shall properly implement, operate and maintain all the best management practices. Maintenance shall include inspections of all erosion and sedimentation control after each runoff event and on a weekly basis. All preventative and remedial maintenance work, including clean out, repair, replacement, regrading, reseeding, remulching, and renetting, must be performed immediately.
- 6. An area shall be considered to have achieved final stabilization when it has a minimum uniform 70% perennial vegetative cover or other permanent non-vegetative cover with a density sufficient to resist accelerated surface erosion and subsurface characteristics sufficient to resist sliding or other movements.
- 7. Mulch with mulch control netting or erosion control blankets must be installed on all slopes greater than 3:1.

2-1 COMPOST FILTER SOCK

- 1. Compost sock should be placed parallel to contours with both ends of the sock extended upslope at a 45 degree angle to the rest of the sock to prevent end-arounds.
- 2. Socks placed on earthen slopes should be anchored with stakes driven through the center of the sock or immediately down slope of the sock as per detail.
- 3. Any section of compost sock, which has been undermined or

3-0 CONSTRUCTION SEQUENCE NOTES

- 1. All earth disturbance activities shall proceed in accordance with the following sequence. Each stage shall be completed in compliance with Chapter 102 regulations before any following stage is initiated. Clearing and grubbing shall be limited only to those areas described in each stage.
- 2. Flag the limit of disturbance.
- 3. Install Construction Entrance.
- 4. Install compost filter sock as per plan.
- Mobilize construction equipment.
- 6. Clear and grub the site within the limits of disturbance.
- 7. Strip topsoil and stockpile and stabilize.

8. Complete demolition of the building.

- 9. Backfill and compact clean fill, spread 4" topsoil, seed and mulch.
- 10. After site is stabilized, remove temporary BMP's and stabilize.

4.0 GROUND COVER

- 4.1 Temporary Seeding
- 1. All grass areas disturbed by the work of this Project shall be seeded as follows:
- 2. Temporary seeding shall be done in areas where active work will not be performed for twenty days (20). Temporary seeding shall be done immediately after work ceases.
- 3. Apply agricultural lime and fertilizer as follows for temporary
- 3.1. Agricultural Lime -- 50 pounds per 1,000 square feet 3.2. Fertilizer -- 12 pounds per 1,000 square feet
- 4. Fertilizer shall be a commercial type 10-20-20.
- 5. Temporary seed mixture Annual Ryegrass -- 1 pound per 1,000 square feet.
- 6. All temporary seeding shall be mulched. Temporary seeding shall be watered as required to develop cover.
- 7. Mulch shall be straw, shall be clean and free from noxious weeds, and shall be applied at the rate of 140 pounds per 1,000 square

4.2 Permanent Seeding

- 1. Permanent seeding shall take place in all disturbed areas as
- 2. Fertilization: The following shall be spread and worked into the topsoil to a depth of 3 to 4 inches.
- 2.1. Agricultural Lime 275 pounds per 1,000 square feet 2.2. Fertilizer - 25 pounds per 1,000 square feet
- 3. The fertilizer shall be a commercial type 10-20-20.
- **4. Note:** If agricultural lime and fertilizer have been applied previously to the ground where the permanent seed is to be applied, the lime and fertilizer rates shall be reduced by the amount by what has been applied previously.
- 5. Permanent Seed Mixture: The following seed mixtures shall be applied as follows:
- 6. PENNDOT Formula L Low Grow Mix
- 6.1. 35% Creeping Red Fescue 6.2. 27.5% Defiant Hard Fescue 6.3. 27.5% Stonehenge Fescue
- 6.4. 10% Annual Ryegrass 7. **Mulch:** Apply mulch to all permanently seeded areas.
- 7.1. Materials: Straw, air-dried and free from undesirable seeds and course materials. Application: 140 pounds per 1,000

5.0 MAINTENANCE PROGRAM

5.1 Emergency Erosion Protection


- 1. If erosion does occur, the contractor shall repair and reseed those areas or use other stabilization methods as required. The contractor shall use jute, wood fiber, or other tie down filter netting on top of the new seed as required, regardless of the slope of the
- 2. Mulched areas shall be checked weekly and immediately after severe storms for damage, until the mulching is no longer necessary for protection against erosion. Damaged portions of the mulch or tie down materials shall be repaired as soon as discovered.


5.2 Periodic Inspection Program

1. The contractor will regularly inspect the Project's erosion and tation controls during the entire active construction stages. The inspections will be performed weekly or after all runoff events and the inspections shall be documented and records of repairs keep on site. The contractor will be responsible for the installation, operation, maintenance, and removal of all erosion and sedimentation controls. All preventative and remedial maintenance work, including clean out repair, replacement, regrading, reseeding, remulching, and renetting must be performed immediately. Sediment that has been trapped by the silt soxx will be removed as required, and in all cases, before the accumulation has reached half the height of the BMP. Compost filter sock will be re-anchored, repaired, or replaced as necessary. All other controls will be inspected on the same schedule. If erosion and sediment control BMPs fail to perform as expected, replacement BMPs, or modification of those installed will be required.

5.3 Removal of Controls and Continuing Maintenance

- 1. All required temporary erosion and sedimentation controls shall remain in place and be maintained until the area they protect has been stabilized.
- 2. An area shall be considered to have achieved final stabilization when it has a minimum uniform 70% perennial vegetative cover or other permanent non-vegetative cover with a density sufficient to resist accelerated surface erosion and subsurface characteristics sufficient to resist sliding or other movements.






SECTION

MAINTENANCE NOTES:

- 1. THE CONTRACTOR SHALL MAINTAIN THE SEDIMENT CONTROL IN A FUNCTIONAL CONDITION AT ALL TIMES AND IT SHALL BE ROUTINELY INSPECTED. 2. IF THE SEDIMENT CONTROL HAS BEEN DAMAGED, IT SHALL BE REPAIRED, OR
- REPLACED IF BEYOND REPAIR. 3. THE CONTRACTOR SHALL REMOVE SEDIMENT AT THE BASE OF THE UPSLOPE SIDE OF THE SEDIMENT CONTROL WHEN ACCUMULATION HAS REACHED ¹/₂ OF THE EFFECTIVE HEIGHT OF THE SEDIMENT CONTROL, OR AS DIRECTED BY THE ENGINEER. ALTERNATIVELY, A NEW SEDIMENT CONTROL CAN BE PLACED ON TOP OF AND SLIGHTLY BEHIND THE ORIGINAL ONE CREATING MORE SEDIMENT STORAGE CAPACITY WITHOUT SOIL DISTURBANCE.
- 4. SEDIMENT CONTROL SHALL BE MAINTAINED UNTIL DISTURBED AREA ABOVE THE DEVICE HAS BEEN PERMANENTLY STABILIZED AND CONSTRUCTION ACTIVITY HAS 5. THE FILTERMEDIA WILL BE DISPERSED ON SITE ONCE DISTURBED AREA HAS BEEN
- PERMANENTLY STABILIZED, CONSTRUCTION ACTIVITY HAS CEASED, OR AS DETERMINED BY THE ENGINEER. 6. FOR LONG-TERM SEDIMENT AND POLLUTION CONTROL APPLICATIONS, SEDIMENT CONTROL CAN BE SEEDED AT THE TIME OF INSTALLATION TO CREATED A VEGETATIVE FILTERING SYSTEM FOR PROLONGED AND INCREASED FILTRATION OF SEDIMENT AND SOLUBLE POLLUTANTS (CONTAINED VEGETATIVE FILTER STRIP). THE APPROPRIATE SEED MIX SHALL BE DETERMINED BY THE ENGINEER.





50' (MIN.)

EXG. ASPHALT ROAD -


** MOUNTABLE BERM USED TO PROVIDE PROPER COVER FOR PIPE. ** VEHICLES AND EQUIPMENT MAY NEITHER ENTER DIRECTLY TO NOR EXIT DIRECTLY FROM THE SITE WITHOUT PASSING THRU A ROCK CONSTRUCTION ENTRANCE.

PLAN

- REMOVE TOPSOIL PRIOR TO INSTALLATION OF ROCK CONSTRUCTION ENTRANCE. EXTEND ROCK OVER FULL WIDTH OF ENTRANCE.
- RUNOFF SHALL BE DIVERTED FROM ROADWAY TO A SUITABLE SEDIMENT REMOVAL BMP PRIOR TO ENTERING ROCK CONSTRUCTION ENTRANCE.
- MOUNTABLE BERM SHALL BE INSTALLED WHEREVER OPTIONAL CULVERT PIPE IS USED AND PROPER PIPE COVER AS SPECIFIED BY MANUFACTURER IS NOT OTHERWISE PROVIDED. PIPE SHALL BE SIZED APPROPRIATELY FOR SIZE OF DITCH BEING CROSSED.

MAINTENANCE: ROCK CONSTRUCTION ENTRANCE THICKNESS WILL BE CONSTANTLY MAINTAINED TO THE SPECIFIED DIMENSIONS BY ADDING ROCK. A STOCKPILE OF ROCK MATERIAL WILL BE MAINTAINED ON THE SITE FOR THIS PURPOSE. ALL SEDIMENT DEPOSITED ON PAVED ROADWAYS SHALL BE REMOVED AND RETURNED TO THE CONSTRUCTION SITE IMMEDIATELY. IF EXCESSIVE AMOUNTS OF SEDIMENT ARE BEING DEPOSITED ON ROADWAY, EXTEND LENGTH OF ROCK CONSTRUCTION ENTRANCE BY 50' INCREMENTS UNTIL CONDITION IS ALLEVIATED OR INSTALL WASH RACK. WASHING THE ROADWAY OR SWEEPING THE DEPOSITIS INTO ROADWAY DITCHES, SEWERS, CULVERTS, OR OTHER DRAINAGE COURSES IS NOT ACCEPTABLE.





COMMONWEALTH OF PENNSYLVANIA DEPT. OF MILITARY & VETERAN'S AFFAIRS ANNVILLE, PENNSYLVANIA 17003

|DESIGN PROFESSIONALS:

PROJECT NO.:

OFFICE OF FACILITIES AND ENGINEERING BUREAU OF DESIGN AND PROJECT MANAGEMENT BLDG. 0-10, FORT INDIANTOWN GAP ANNVILLE, LEBANON COUNTY, PENNSYLVANIA

VERIFY SCALE BAR IS ONE (1) INCH LONG ON ORIGINAL DRAWING:

IF BAR IS NOT ONE (1) INCH LONG, ADJUST SCALE ACCORDINGLY

ALL DIMENSIONS.

VARIANCE FROM CONTRACT

DOCUMENTS NOT PERMITTED

AND ARCHITECTURE APPROVAL.

DEMOLITION BIDDLE AIR GUARD STATION MONTGOMERY CO, HORSHAM, PENNSYLVANIA 19044

BLDG. 201

NOTES & DETAILS

CONTRACTOR SHALL FIELD VERIFY DRAWN BY K. LLOYD 1 APR 2023 CHECKED BY WITHOUT BUREAU OF ENGINEERING L. STEFANIK | AS NOTED

DRAWING NO. C.2.0

ZAWA 192006 / 42220185