

**EAST STROUDSBURG UNIVERSITY OF PENNSYLVANIA  
STATE SYSTEM OF HIGHER EDUCATION  
COMMONWEALTH OF PENNSYLVANIA**

**ADDENDUM NUMBER 3  
Project Number: ESU 30-1436**

Issue Date: 25 July 2014

Project Title: Replace Chiller, Koehler Fieldhouse and Natatorium

Location: East Stroudsburg University, East Stroudsburg, Monroe County, Pennsylvania

This Addendum forms a part of the Contract Documents and modifies the original Bidding Documents (Project Manual, Drawings and Specifications dated 5 June, 2014). Bidders must acknowledge receipt of any and all Addenda in the space provided on the Bid Form. Failure to do so may result in rejection of the Bid.

This Addendum refers to and is intended to take precedence over, clarify, revise or add to those portions of the specifications and drawings to which it refers. All requirements of the Project Manual remain unchanged except as cited below:

**Bid Opening Date and Time:** The bid due date and time are hereby extended to **14 August 2014 at 2:00 PM** (local time).

**GENERAL:**

This Addendum is hereby issued and addresses the following:

1. Extend Bid date and bid opening date as noted above.
2. The Substantial Completion date for the project is changed to **February 16, 2015**.
3. New project drawings will be issued approximately **5 August 2014 in Addendum No. 4**.

**PROJECT MANUAL CHANGES:**

**Section / Page / Paragraph**

**Description**

Standard Form of Contract for Construction Between the System and the Contractor / 2 of 5 / Top

Revised the "**substantially complete the Work** (Substantial Completion) **not later than January 15, 2015**" to read "**substantially complete the Work** (Substantial Completion) **not later than February 16, 2015**"

23 05 29 / 1 / 3.2, Item E

Revised to read "1. Install ITW Redhead Multi-Set II Type RX drop-in threaded inserts anchors in precast plank or as available by the listed manufacturers. Install fasteners according to manufacturer's written instructions."

- 23 05 29 / 2 / 3.2, Item E Deleted "2. Install mechanical-expansion anchors in concrete after concrete is placed and completely cured. Install fasteners according to manufacturer's written instructions."
- 23 07 16 / All / Footer Revised the Section Number "23 02 29" to read "23 07 16"
- 23 64 23 / 4 / 2.1, Item E.4 Deleted ", plus hot-gas bypass"
- 23 64 23 / 5 / 2.2, Item J.1 Deleted "b. Coat coils with a baked epoxy corrosion-resistant coating after fabrication."
- 23 64 23 / 8 / 2.1, Item B Deleted "1. Allow Owner access to place where water chillers are being tested. Notify Architect 14 days in advance of testing."

**END ADDENDUM NO. 3**