

ATTACHMENT A  
SCOPE OF WORK  
WATER LINE INSTALLATION  
RFX:

**Excavation & Restoration:**

- Remove existing asphalt paving where new water line crosses road
- Provide 24" wide by 40" deep trench approximately 250' long for new water line
- Run 4-6" of screenings in trench before the installation of water line
- Run 4-6" of screenings above new water line after installation
- Provide compacted (natural material) backfill for remainder of trench depth
- Provide restoration of all disturbed lawn and parking lot areas
- Provide asphalt paving repair across driveway
  - Includes 4" of 19mm binder and 1.5" of 9.5mm wearing course WMA

**Installation:**

- Provide new water meter pit, meter, meter horn, and hot tap existing water main (all labor and materials provided by Water Authority)
- Provide approximately 250' of 2" DR9 poly water line and tie into existing line for brine maker at truck wash building
- Provide new curb box with 2" shutoff valve outside water tower fence
- Provide all water line fittings as required for the new service
- Upon completion, test water line of tie-in

\*Does not include any work in existing brine making building